

Planck Early Results: Origin of the submm excess dust emission in the Magellanic Clouds

Planck Collaboration: P. A. R. Ade⁶⁹, N. Aghanim⁴⁵, M. Arnaud⁵⁵, M. Ashdown^{53,75}, J. Aumont⁴⁵, C. Baccigalupi⁶⁷, A. Balbi²⁸, A. J. Banday^{73,6,60}, R. B. Barreiro⁵⁰, J. G. Bartlett^{3,51}, E. Battaner⁷⁷, K. Benabed⁴⁶, A. Benoît⁴⁶, J.-P. Bernard^{73,6} *, M. Bersanelli^{26,40}, R. Bhatia³³, J. J. Bock^{51,7}, A. Bonaldi³⁶, J. R. Bond⁵, J. Borrill^{59,70}, C. Bot⁶⁵, F. R. Bouchet⁴⁶, F. Boulanger⁴⁵, M. Bucher³, C. Burigana³⁹, P. Cabella²⁸, J.-F. Cardoso^{56,3,46}, A. Catalano^{3,54}, L. Cayón¹⁹, A. Challinor^{76,53,8}, A. Chamballu⁴³, L.-Y. Chiang⁴⁷, C. Chiang¹⁸, P. R. Christensen^{63,29}, D. L. Clements⁴³, S. Colombi⁴⁶, F. Couchot⁵⁸, A. Coulaiss⁵⁴, B. P. Crill^{51,64}, F. Cuttaia³⁹, L. Danese⁶⁷, R. D. Davies⁵², R. J. Davis⁵², P. de Bernardis²⁵, G. de Gasperis²⁸, A. de Rosa³⁹, G. de Zotti^{36,67}, J. Delabrouille³, J.-M. Delouis⁴⁶, F.-X. Désert⁴², C. Dickinson⁵², K. Dobashi¹³, S. Donzelli^{40,48}, O. Doré^{51,7}, U. Dörl⁶⁰, M. Douspis⁴⁵, X. Dupac³², G. Efstathiou⁷⁶, T. A. Enßlin⁶⁰, F. Finelli³⁹, O. Forni^{73,6}, M. Frailis³⁸, E. Franceschi³⁹, Y. Fukui¹⁷, S. Galeotta³⁸, K. Ganga^{3,44}, M. Giard^{73,6}, G. Giardino³³, Y. Giraud-Héraud³, J. González-Nuevo⁶⁷, K. M. Górski^{51,79}, S. Gratton^{53,76}, A. Gregorio²⁷, A. Gruppuso³⁹, D. Harrison^{76,53}, G. Helou⁷, S. Henrot-Versillé⁵⁸, D. Herranz⁵⁰, S. R. Hildebrandt^{7,57,49}, E. Hivon⁴⁶, M. Hobson⁷⁵, W. A. Holmes⁵¹, W. Hovest⁶⁰, R. J. Hoyland⁴⁹, K. M. Huffenberger⁷⁸, A. H. Jaffe⁴³, W. C. Jones¹⁸, M. Juvela¹⁶, A. Kawamura¹⁷, E. Keihänen¹⁶, R. Keskkitalo^{51,16}, T. S. Kisner⁵⁹, R. Kneissl^{31,4}, L. Knox²¹, H. Kurki-Suonio^{16,34}, G. Lagache⁴⁵, A. Lähteenmäki^{1,34}, J.-M. Lamarre⁵⁴, A. Lasenby^{75,53}, R. J. Laureijs³³, C. R. Lawrence⁵¹, S. Leach⁶⁷, R. Leonardi^{32,33,22}, C. Leroy^{45,73,6}, M. Linden-Vørnle¹⁰, M. López-Caniego⁵⁰, P. M. Lubin²², J. F. Macías-Pérez⁵⁷, C. J. MacTavish⁵³, S. Madden⁵⁵, B. Maffei⁵², N. Mandolesi³⁹, R. Mann⁶⁸, M. Maris³⁸, E. Martínez-González⁵⁰, S. Masi²⁵, S. Matarrese²⁴, F. Matthai⁶⁰, P. Mazzotta²⁸, P. R. Meinhold²², A. Melchiorri²⁵, L. Mendes³², A. Mennella^{26,38}, M.-A. Miville-Deschênes^{45,5}, A. Moneti⁴⁶, L. Montier^{73,6}, G. Morgante³⁹, D. Mortlock⁴³, D. Munshi^{69,76}, A. Murphy⁶², P. Naselsky^{63,29}, F. Nati²⁵, P. Natoli^{28,2,39}, C. B. Netterfield¹², H. U. Nørgaard-Nielsen¹⁰, F. Noviello⁴⁵, D. Novikov⁴³, I. Novikov⁶³, T. Onishi¹⁴, S. Osborne⁷², F. Pajot⁴⁵, R. Paladini^{71,7}, D. Paradis^{73,6}, F. Pasian³⁸, G. Patanchon³, O. Perdereau⁵⁸, L. Perotto⁵⁷, F. Perrotta⁶⁷, F. Piacentini²⁵, M. Piat³, S. Plaszczynski⁵⁸, E. Pointecouteau^{73,6}, G. Polenta^{2,37}, N. Ponthieu⁴⁵, T. Poutanen^{34,16,1}, G. Prézeau^{7,51}, S. Prunet⁴⁶, J.-L. Puget⁴⁵, W. T. Reach⁷⁴, R. Rebolo^{49,30}, M. Reinecke⁶⁰, C. Renault⁵⁷, S. Ricciardi³⁹, T. Riller⁶⁰, I. Ristorcelli^{73,6}, G. Rocha^{51,7}, C. Rosset³, M. Rowan-Robinson⁴³, J. A. Rubiño-Martín^{49,30}, B. Rusholme⁴⁴, M. Sandri³⁹, G. Savini⁶⁶, D. Scott¹⁵, M. D. Seiffert^{51,7}, G. F. Smoot^{20,59,3}, J.-L. Starck^{55,9}, F. Stivoli⁴¹, V. Stolyarov⁷⁵, R. Sudiwala⁶⁹, J.-F. Sygnet⁴⁶, J. A. Tauber³³, L. Terenzi³⁹, L. Toffolatti¹¹, M. Tomasi^{26,40}, J.-P. Torre⁴⁵, M. Tristram⁵⁸, J. Tuovinen⁶¹, G. Umana³⁵, L. Valenziano³⁹, J. Varis⁶¹, P. Vielva⁵⁰, F. Villa³⁹, N. Vittorio²⁸, L. A. Wade⁵¹, B. D. Wandelt^{46,23}, N. Ysard¹⁶, D. Yvon⁹, A. Zacchei³⁸, and A. Zonca²²

(Affiliations can be found after the references)

Preprint online version: January 12, 2011

ABSTRACT

The integrated Spectral Energy Distributions (SED) of the Large Magellanic Cloud (LMC) and Small Magellanic Cloud (SMC) appear significantly flatter than expected from dust models based on their far-infrared and radio emission. The origin of this millimetre excess is still unexplained, and is here investigated using the *Planck* data. The integrated SED of the two galaxies before subtraction of the foreground (Milky Way) and background (CMB fluctuations) emission are in good agreement with previous determinations, confirming the presence of the millimetre excess. The background CMB contribution is subtracted using an Internal Linear Combination (ILC) method performed locally around the galaxies. The foreground emission from the Milky Way is subtracted as a Galactic H I template and the dust emissivity is derived in a region surrounding the two galaxies and dominated by Milky Way emission. After subtraction, the remaining emission of both galaxies correlates closely with the atomic and molecular gas emission of the LMC and SMC. The millimetre excess in the LMC can be explained by CMB fluctuations, but a significant excess is still present in the SMC SED.

The *Planck* and *IRAS-IRIS* data at 100 μm are combined to produce thermal dust temperature and optical depth maps of the two galaxies. The LMC temperature map shows the presence of a warm inner arm already found with the *Spitzer* data, but also shows the existence of a previously unidentified cold outer arm. Several cold regions are found along this arm, some of which are associated with known molecular clouds. The dust optical depth maps are used to constrain the thermal dust emissivity power law index (β). The average spectral index is found to be consistent with $\beta = 1.5$ and $\beta = 1.2$ below 500 μm for the LMC and SMC respectively, significantly flatter than the values observed in the Milky Way. Furthermore, there is evidence in the SMC for a further flattening of the SED in the sub-mm, unlike for the LMC where the SED remains consistent with $\beta = 1.5$. The spatial distribution of the millimetre dust excess in the SMC follows the gas and thermal dust distribution.

Different models are explored in order to fit the dust emission in the SMC. It is concluded that the millimetre excess is unlikely to be caused by very cold dust emission and that it could be due to a combination of spinning dust emission and thermal dust emission by more amorphous dust grains than those present in our Galaxy.

Key words. ISM: general, dust, extinction, clouds – Galaxies: ISM – Infrared: ISM – Submillimeter: ISM

1. Introduction

Star formation and the exchange and evolution of materials between the stars and the interstellar medium (ISM) are continuous

* Corresponding author; email: Jean-Philippe.Bernard@cesr.fr.

processes that drive the evolution of galaxies. As stars evolve, die and renew the life cycle of dust and gas, the amount of dust and its distribution in a galaxy has important consequences for its subsequent star formation. Thus knowing the dust content throughout cosmic history would provide clues to the star formation history of the universe as the metallicities evolve. One of the puzzling results that has emerged from the studies of dust SEDs in the early universe, is finding very high dust masses in high redshift galaxies. For example, recent *Herschel* observations of submillimetre galaxies (SMGs) find excessively high dust masses, and high dust-to-gas mass ratios (D/G) (Santini et al. 2010). These findings contradict the low metallicities measured in the gas. Large dust masses have also been measured for a range of low metallicity local universe dwarf galaxies (Dumke et al. 2003; Galliano et al. 2003, 2005; Bendo et al. 2006; Galametz et al. 2009; Grossi et al. 2010; O'Halloran et al. 2010). Our understanding of how dust masses are estimated and what observational constraints are necessary is called into question by the discovery that the dust masses measured in these galaxies appear significantly higher than expected from their metal content.

Excessively large dust masses only seem to be found in low metallicity galaxies to date. The evidence is found in the behavior of the submillimetre (submm) emission, beyond about 400 – 500 μm . From a study of a broad range of metal-rich and metal-poor galaxies observed with wide wavelength coverage that included submm observations beyond 500 μm , a submm excess, beyond the normal dust SED models, was found only for low metallicity systems (Galametz et al. 2010). Such submm excess is particularly evident in the Magellanic Clouds (Israel et al. 2010; Bot et al. 2010b). The origin of such excess is still uncertain but several suggestions have been put forward:

- The submm excess has been modeled as a cold dust component with a submm emissivity index (β) of $\beta=1$, which suggests a low dust temperature of ~ 10 K (Galliano et al. 2003, 2005; Galametz et al. 2009, 2010). There are few observational constraints in the submm wavelength window, hence this cold component is a rather ad hoc solution. This description often results in discrepantly large D/G ratios being found for the low metallicity galaxies if the estimates of the total gas reservoir are well known.
- Meny et al. (2007) show that emission by amorphous grains is expected to produce excess emission in the submm. As a result, the spectral shape of emission by amorphous grains cannot be reproduced by a single emissivity index over the whole Far-Infrared (FIR) to millimetre (mm) range, and is expected to flatten at long wavelengths. The intensity of the excess is also predicted to depend strongly on the temperature of the dust grains. Modifying the dust optical properties to incorporate the effects of the disordered structure of the amorphous grains, showed that the effective submm emissivity index decreases (thus flattening the submm Rayleigh-Jeans slope) as the dust temperature increases. Similarly, an inverse correlation between the dust temperature and the spectral index has been observed in data from the FIR to the submm (e.g. Dupac et al. 2003; Paradis et al. 2010). However, these authors as well as Shetty et al. (2009a) advise caution in the interpretation of the observed inverse T - β relationship, which is affected by the natural correlation between these two parameters, and requires careful treatment of observational uncertainties. Shetty et al. (2009b) also studied the effect on the observed T - β relation of temperature variations along the line-of-sight. Paradis et al. (2009) using the *DIRBE*, *Archeops* and *WMAP* data showed that the FIR-

submm SEDs of galactic molecular clouds and their neutral surroundings indeed show a flattening beyond $\lambda \approx 500$ μm .

- Spinning dust emitted in the ionised gas of galaxies has been suggested as the explanation for the radio emission often seen in galaxies (Ferrara & Dettmar 1994). This idea was further explored by Anderson & Watson (1993) and Draine & Lazarian (1998b,a) who characterized the 10 to 100 GHz anomalous foreground emission component as spinning dust from very small dust particles such as Polycyclic Aromatic Hydrocarbons (PAHs). Recent improvements to the model suggest the peak frequency, which could occur in the submm, depends on many parameters, including the radiation field intensity, the dust size distribution, the dipole moment distribution, the physical parameters of the gas phases, etc. (Hoang et al. 2010; Silsbee et al. 2010; Ysard et al. 2010; Ysard & Verstraete 2010a). Spinning dust has been a preferred explanation for the submm excess observed on the global scale in the Magellanic Clouds (Israel et al. 2010; Bot et al. 2010b).
- ? have suggested hydrogenated amorphous carbon as the most likely carbonaceous grain material instead of graphite. The advantage of using amorphous carbon, particularly in the cases where a submm excess is found, is that amorphous carbons are more emissive and result in a flatter submm slope and less dust mass. This has been used with new *Herschel* observations to model some low metallicity galaxies (Galametz et al. 2010; O'Halloran et al. 2008; Meixner et al. 2010).
- The enhancement of hot, very small, stochastically heated grains with a low dust emissivity, has also been suggested to characterize the submm emission when there is a submm excess present (Lisenfeld et al. 2001; Zhu et al. 2009).

Some of the possible causes of the submm excess could be ruled out or constrained if the gas mass estimates were better established. However, estimates of the total gas reservoir in low metallicity environments have been uncertain, particularly the molecular gas component. Observations of CO in low metallicity galaxies have been a challenge, and the dearth of detected CO has often been interpreted as meaning there is very little mass in molecular gas present in galaxies which are otherwise actively forming massive stars (Leroy et al. 2009). However, relying on CO alone to trace the H_2 mass could potentially miss a large reservoir of molecular gas residing outside the CO-emitting region, as indicated by the FIR fine structure observations in the Magellanic Clouds and other low metallicity galaxies (e.g. Poglitsch et al. 1995; Madden et al. 1997; Madden 2000). The presence of a hidden gas mass in low metallicity galaxies is also suggested by dust observations of the Magellanic Clouds (e.g. Bernard et al. 2008; Dobashi et al. 2008; Leroy et al. 2007; Roman-Duval et al. 2010; Bot et al. 2010a).

Most of these studies which find a submm excess in low-metallicity galaxies are derived from models on global galaxy scales and use data with a wavelength coverage that is limited to $\lambda < 500$ μm with *Herschel* or to $\lambda < 870$ μm for ground-based observations. The Galametz et al. (2010) study demonstrated that dust masses can differ by an order of magnitude depending on the availability of submm constraints on the SED modelling. These require wider wavelength coverage of the submm and millimetre (mm) region and better spatial information, to map out the submm excess and determine the local physical conditions.

The closest low-metallicity galaxies are our neighboring Large Magellanic Cloud (LMC) and Small Magellanic Cloud (SMC), which have metallicities of 50% and 20% solar metal-

licity ($Z_{\odot}$) respectively. They are ideal laboratories for studying the ISM and star formation in different low metallicity environments. Recent studies with *Spitzer* (SAGE: Meixner et al. 2006; Bolatto et al. 2007) and *Herschel* (HERITAGE: Meixner et al. 2010) have mapped out the temperature and dust mass distribution (Bernard et al. 2008; Gordon et al. 2009, 2010; Leroy et al. 2007). Recent *Herschel* studies of the LMC already point to a possible submm band excess and an excessive dust mass, which may be suggesting the presence of molecular gas not probed by CO. This could be explained by the presence of amorphous carbon grains (Roman-Duval et al. 2010; Meixner et al. 2010; Gordon et al. 2010). It was difficult to be conclusive about the cause of the excess seen in the *Herschel* observation because of the lack of longer wavelength coverage. Global excess mm and submm emission in the LMC and SMC was indisputably shown by Bot et al. (2010b) and Israel et al. (2010) using broader wavelength coverage that included the submm to cm observations of the Top-Hat balloon experiment, *WMAP* and *COBE* and their results favour spinning dust as the explanation for the submm and mm excess, but require additional spatial coverage to be firmly conclusive. *Planck*¹ observations have both wide wavelength coverage and the spatial resolution to locate the submm emission within the LMC and SMC, which will help determine the origin of the submm excess.

2. Observations

2.1. Planck data

The *Planck* first mission results are presented in The Planck Collaboration (2011a) and the in-flight performances of the two focal plane instruments *HFI* (High Frequency Instrument) and *LFI* (Low Frequency Instrument) are given in The Planck Collaboration (2011e) and The Planck Collaboration (2011d) respectively. The data processing and calibration of the *HFI* and *LFI* data used here is described in The Planck Collaboration (2011g) and The Planck Collaboration (2011h) respectively.

Figure 1 shows the total intensity maps observed toward the LMC and SMC at a few *HFI* and *LFI* frequencies. Both galaxies are well detected at high frequencies. Around 100 GHz, their emission can barely be distinguished from CMB fluctuations. At lower frequencies, the contrast between the galaxies' emission and the CMB fluctuations becomes larger again. Note that the apparent variation of the noise level at a constant right-ascension value across the LMC is real and is due to the LMC being positioned at the edge of the *Planck* deep field.

The *Planck* DR2 data have had the CMB fluctuations removed in a way which is inappropriate for detailed examination of some foreground sources like the LMC and SMC. We therefore use the original data before CMB subtraction (version DX4 of the *Planck*-*HFI* and *Planck*-*LFI* data) and perform our own subtraction of the CMB fluctuations, based on a local ILC (see Sec. 2.3.2).

We use the internal variance (σ_{Π}^2) provided with the *Planck* data, which represents the white noise on the intensity. The LMC and SMC have been observed many times, as the *Planck* scanning strategy (The Planck Collaboration 2011a) covers the region close to the ecliptic pole repeatedly. In particular, the LMC

Table 1. Characteristics of the FIR/submm data used in this study.

Data	λ_{ref} [μm]	ν_{ref} [GHz]	θ [arcmin]	σ_{Π} [MJy sr ⁻¹]	σ_{abs} [%]
<i>IRAS</i>	100	2997.92	4.30	0.06 ^{†‡}	13.6 [‡]
<i>HFI</i>	349.82	857	3.67	0.12 ^b	7%
<i>HFI</i>	550.08	545	3.80	0.12 ^b	7%
<i>HFI</i>	849.27	353	4.43	0.08 ^b	$\lesssim 2\%$
<i>HFI</i>	1381.5	217	4.68	0.08 ^b	$\lesssim 2\%$
<i>HFI</i>	2096.4	143	7.04	0.08 ^b	$\lesssim 2\%$
<i>HFI</i>	2997.9	100	9.37	0.07 ^b	$\lesssim 2\%$
<i>LFI</i>	4285.7	70.3	13.01	–	5.0
<i>LFI</i>	6818.2	44.1	27.92	–	5.0
<i>LFI</i>	10000	28.5	32.65	–	5.0
<i>WMAP</i>	3200	93.69	13.2	1.76 [‡]	1.0
<i>WMAP</i>	4900	61.18	21.0	0.36 [‡]	1.0
<i>WMAP</i>	7300	41.07	30.6	0.11 [‡]	1.0
<i>WMAP</i>	9100	32.94	39.6	0.05 [‡]	1.0
<i>WMAP</i>	13000	23.06	52.8	0.02 [‡]	1.0

[†] Assumed to be for the average *IRAS* coverage. σ_{Π} computed by rescaling this value to actual coverage

[‡] From Miville-Deschênes & Lagache (2005)

^b 1σ average value in one beam scaled from The Planck Collaboration (2011g). We actually use the internal variance maps for σ_{Π}

[‡] From Bennett et al. (2003)

is located at the boundary of the *Planck* deep field. Its eastern half has a much higher signal to noise ratio than its western half. We assume the absolute uncertainties from calibration given in The Planck Collaboration (2011g) and The Planck Collaboration (2011h) for *HFI* and *LFI* respectively and summarized in Table 1.

2.2. Ancillary data

2.2.1. H I LMC/SMC data

To trace the atomic gas in the Magellanic Clouds, we used H I maps in the 21cm line, obtained by combining data from the Australia Telescope Compact Array (ATCA) and the Parkes single dish telescope. For the LMC, this data was obtained by Kim et al. (2003) and Staveley-Smith et al. (2003) and covers $11.1^{\circ} \times 12.4^{\circ}$ on the sky. The spatial resolution is $1'$ corresponding to a physical resolution of about 14.5 pc at the distance of the LMC. For the SMC, the data was obtained by Staveley-Smith et al. (1997) and Stanimirovic et al. (1999). It covers a $4.5^{\circ} \times 4.5^{\circ}$ region. H I observations of the SMC tail ($7^{\circ} \times 6^{\circ}$) were obtained by Muller et al. (2003) and combined to the one in the direction of the SMC. The spatial resolution is $98''$, corresponding to 30pc at the distance of the SMC.

2.2.2. H I Galactic data

The LMC and SMC are located at galactic latitudes $b_{\Pi} = -34^{\circ}$ and $b_{\Pi} = -44^{\circ}$ respectively. They can therefore suffer from significant contamination by Galactic foreground emission, which has to be removed from the IR data. In order to account for the Galactic foreground emission, we used Galactic H I column density maps.

For the LMC, the H I foreground map was constructed by Staveley-Smith et al. (2003) by integrating the Parkes H I data

¹ *Planck* (<http://www.esa.int/Planck>) is a project of the European Space Agency (ESA) with instruments provided by two scientific consortia funded by ESA member states (in particular the lead countries: France and Italy) with contributions from NASA (USA), and telescope reflectors provided in a collaboration between ESA and a scientific consortium led and funded by Denmark.




Fig. 1. *Planck* total Intensity data for the LMC (left) and SMC (right) at 857 (top), 100 (middle) and 28.5 GHz (bottom) at full resolution. The top panels are shown in log scale. The circle in the top panels shows the region used to extract average SEDs.

in the velocity range from $-64 < v_{\text{hel}} < 100 \text{ km s}^{-1}$, which excludes all LMC and SMC associated gas ($v > 100 \text{ km s}^{-1}$) but includes essentially all Galactic emission. The spatial resolution is $14'$. For the SMC, a map of combined *ATCA* and *Parkes* data was built by integrating the Galactic velocities by E. Muller (private communication). The resolution is $98''$.

These maps show that the Galactic foreground across the LMC is as strong as $N_{\text{H}} = 1.3 \times 10^{21} \text{ Hcm}^{-2}$, with significant variation across the LMC, in particular a wide filamentary structure oriented southwest to northeast. The Galactic foreground across the SMC is weaker with values $N_{\text{H}} \approx 3.2 \times 10^{20} \text{ Hcm}^{-2}$ but the associated FIR-submm emission is still non-negligible

since the SMC emission is also weaker than that of the LMC, due to its lower dust and gas content.

These foreground maps are used to subtract the foreground IR emission from the IR maps, using the emissivity SED described in Sect. 2.3.3.

2.2.3. CO data

The $^{12}\text{CO}(J=1\rightarrow 0)$ molecular data used in this work was obtained using the NANTEN telescope, a 4-m radio telescope of Nagoya University at Las Campanas Observatory, Chile (see Fukui et al. 2008). The observed region covers about 30 square degrees where CO clouds were detected in the NANTEN first survey (e.g. Fukui et al. 1999; Mizuno et al. 2001; Fukui et al. 2008). The observed grid spacing was $2'$, corresponding to about 30 and 35 pc at the distance of the LMC and SMC, while the half-power beam width was $2.6'$ at 115 GHz.

We used the CO maps of the Magellanic Clouds to construct an integrated intensity map (W_{CO}), integrating over the full v_{LSR} range of the data ($100 < v_{\text{LSR}} < 400 \text{ km s}^{-1}$ for about 80 % of the data, while the remaining 20 % had a velocity range of about 100 km s^{-1} covering the H I emitting regions.)

2.2.4. H_α data

In order to estimate the free-free contribution to the millimetre fluxes, we used the continuum-subtracted H_α maps from the Southern H-Alpha Sky Survey Atlas (SHASSA, Gaustad et al. 2001) centered on the Magellanic Clouds.

2.2.5. FIR-Submm data

We used the following FIR-submm ancillary data.

- *IRAS-IRIS* (Improved Reprocessing of the *IRAS* Survey) $100 \mu\text{m}$ in order to constrain the dust temperature. The characteristics of this data, including the noise properties were taken from Miville-Deschênes & Lagache (2005) and are summarized in Table 1
- *WMAP* 7yr data. The characteristics of this data, including the noise properties were taken from Bennett et al. (2003) and Jarosik et al. (2010) and are summarized in Table 1

2.3. Additional Data processing

2.3.1. Common angular resolution and pixelisation

For data already available in the HEALPix (Górski et al. 2005) format (e.g., *WMAP*), we obtained the data from the Lambda web site (<http://lambda.gsfc.nasa.gov/>). For data not originally presented in the HEALPix format, the ancillary data were brought to the HEALPix pixelisation, using a method where the surface of the intersection between each HEALPix and FITS pixel of the original data was used as a weight to regrid the data. The HEALPix resolution was chosen so as to match the Shannon sampling of the original data at resolution θ , with a HEALPix resolution set so that the pixel size is $< \theta/2.4$. The ancillary data and the description of their processing will be presented in Paradis & et. al. (2011).

All ancillary data were then smoothed to an appropriate resolution by convolution with a Gaussian smoothing function with appropriate FWHM using the smoothing HEALPix function, and were brought to a pixel size matching the Shannon sampling of the final resolution.

2.3.2. CMB subtraction




Fig. 2. Error due to the ILC CMB subtraction derived from Monte-Carlo simulations for both LMC and SMC at 100 GHz, as a function of the patch size. The values shown are the difference between the recovered and the input CMB divided by the simulated LMC and SMC, both integrated in a 4° ring.

The upper panel in Fig. 3 shows the total intensity maps observed toward the LMC and SMC before CMB subtraction in the *LFI* 70.3 GHz channel. The amplitude of CMB fluctuations is of the order of that of the diffuse emission of the galaxies and it is clear that, in order to study the integrated SED of the LMC and SMC galaxies, an efficient CMB subtraction has to be performed.

The standard CMB-subtracted maps produced by the Data Processing Center (DPC) (The Planck Collaboration 2011g) were not used in this analysis. They were processed by a Needlet Internal Linear Combination (The Planck Collaboration 2011g) (NILC) that left a significant amount of foreground emission in the CMB estimate towards the LMC and the SMC.

For this reason we have subtracted an estimate of the CMB optimized locally for the LMC and SMC regions, as described below. This CMB component was reconstructed through a classical Internal Linear Combination (ILC) by means of Lagrange multipliers (Eriksen et al. 2004). $12^\circ \times 12^\circ$ patches around the LMC and SMC were extracted from the *HFI* CMB frequency channels maps (100, 143, 217 and 353 GHz) reduced to a common resolution (10 arcmin), in units of K_{CMB} . The CMB component obtained on these patches clearly contains less LMC and SMC residual than the standard *HFI* DPC CMB and therefore will less affect the SED determination. The lower panel in Fig. 3 shows the maps after CMB subtraction in the *LFI* 70.3 GHz channel.

We performed Monte-Carlo simulations in order to estimate the error induced on the SED by our CMB removal. The LMC and SMC were simulated as a sum of two correlated components. The first component spatial template is the *IRAS-IRIS* $100 \mu\text{m}$ map. The second component spatial template is the 545 GHz LMC or SMC *Planck* map. Their correlation coefficients are 83% for the LMC and 92% for the SMC. We normalized their fluxes inside a 4° ring to the value of a typical LMC or SMC dust component and a typical millimetre excess at each *HFI* CMB frequency, respectively. 200 independent realizations of a *WMAP* 7yr best fit CMB (Komatsu et al. 2010) and of nomi-




Fig. 3. SMC (left) and LMC (right) total intensity maps before (top) and after (bottom) CMB subtraction in the 70.3 GHz band at the 13.01 arcmin resolution.

nal inhomogeneous *HFI* white noise were added to the synthetic LMC and SMC on patches of varying sizes. For each of these simulations, for each size, our ILC is performed and compared to the input CMB. We estimate the error due to the CMB subtraction in both the LMC and the SMC by comparing the residual in the CMB map to the emission of the two components at a given frequency. Results at 100 GHz are displayed in Fig. 2. For both the LMC and the SMC, the error increases at small and large patch sizes and an optimal patch size with respect to the CMB subtraction can be found at 5° for the LMC and 13° for the SMC. This behavior is due to the fact that the narrower the patch, the lower the contribution of the CMB to the total variance which is to be minimized in the ILC. On the other hand, when their sizes increase, patches include foreground emission which is uncorrelated with the galaxies and has a different spectrum, and thus both small and large patches contribute to the total variance which must be minimized.

For the $12^\circ \times 12^\circ$ patches used in the following analysis, we estimate the error due to CMB subtraction as $10.38 \mu\text{K}_{\text{CMB}}$ and $28.2 \mu\text{K}_{\text{CMB}}$ for the LMC and SMC respectively. In terms of the fraction of the total galaxy brightness, these correspond to 8.1, 6.2, 2.3 and 0.3 % for the LMC and 12.1, 10.7, 6.4 and 1.4 % for the SMC at 100, 143, 217 and 353 GHz, respectively.

2.3.3. Galactic foreground subtraction

The Milky Way (MW) emission is non-negligible compared to the emission of the LMC and SMC. We remove this contribution at all wavelengths using the MW H I template described in Sec. 2.2.2. We first computed the correlation between all FIR-submm data with this template, in the region where both the MW H I template and the CMB estimate are available, but excluding a circular region centered on each galaxy (centre coordinates taken as $\alpha_{2000} = 05^{\text{h}}15^{\text{m}}30^{\text{s}}$, $\delta_{2000} = -68^\circ30'10''$ and $\alpha_{2000} = 01^{\text{h}}04^{\text{m}}16^{\text{s}}$, $\delta_{2000} = -72^\circ51'36''$ for the LMC and SMC respectively) with radius 4.09° and 2.38° for the LMC and SMC respectively. The spectral distribution of this correlation factor, taken to represent the SED of the MW foreground is shown in Fig. 4. The SED is compared to that of the high galactic latitude reference region used in [The Planck Collaboration \(2011s\)](#) in Fig. 4. It can be seen that the two SEDs are similar, although the MW foreground towards the LMC and SMC appears slightly colder and has a relatively stronger non-thermal component in the millimetre. We subtracted the MW foreground from all data using this SED multiplied by the MW H I template over the full map extent. Note that the median foreground H I integrated intensities over the LMC and SMC are $\approx 297 \text{ K km s}^{-1}$ and $\approx 172 \text{ K km s}^{-1}$, which correspond to a brightnesses of




Fig. 4. Average foreground SED in the direction of the LMC and SMC (lower curve) including *IRAS – IRIS* (light blue), *Planck-HFI* (red), *Planck-LFI* (green) and *WMAP* data (dark blue), compared to the SED of the high latitude low column-density MW SED (upper curve) derived in [The Planck Collaboration \(2011s\)](#), which has been scaled up by a factor of 10 for clarity.

3.0 MJy sr⁻¹ and 1.7 MJy sr⁻¹ respectively at 857 GHz. This is of the same order as the average brightness of the galaxies at that frequency (see Table 2). However, most of the MW emission is canceled when subtracting a local background around the galaxies and the differential correction due to the spatial structure of the MW foreground then accounts for about 0.4% and 21% of the LMC and the SMC brightness respectively.

3. Integrated SEDs

The integrated SED of the LMC and SMC before and after CMB subtraction are shown in Fig. 5 (red and blue diamonds, respectively). They were computed by averaging values in the circular area around each galaxy defined in Sec. 2.3.3, and subtracting an estimate of the sky off the source taken in an annulus with radius 1°. They are compared to the data taken from [Israel et al. \(2010\)](#) and [Bot et al. \(2010b\)](#), which were integrated over the same region. It can be seen that the flux observed in the HFI and LFI bands is consistent with that obtained with previous studies in this wavelength range before subtraction of the CMB fluctuations. A model of thermal dust, free-free and synchrotron emission is fitted to the data as follows. As in [Bot et al. \(2010b\)](#), the thermal dust emission is adjusted according to the [Draine & Li \(2007\)](#) dust model. The free-free emission is deduced from the H_α integrated flux, using the expression from [Hunt et al. \(2004\)](#), assuming an electronic temperature $T_e = 10^4$ K, the ratio of ionized helium to hydrogen $n_{\text{He}^+}/n_{\text{H}^+} = 0.087$, and no extinction. The synchrotron emission was fitted to the radio data from the literature as in [Israel et al. \(2010\)](#). The combined dust, free-free and synchrotron emission is shown by the blue line. It can be seen from Fig. 5 that the SED after subtraction of the CMB fluctuations is in fact compatible with no millimeter emission excess for the LMC, for this particular model. However, the CMB-subtracted SED still shows a significant excess for the SMC, with most data points above $\lambda \approx 1$ mm being in excess over the model by more than 5σ , leading to an overall significance of the excess of about 50σ .

The CMB subtraction removes part of the millimetre excess in both galaxies. This shows that CMB fluctuations behind the

Table 3. Dust temperature, β values and fit reduced χ^2 for various methods experimented to derive the temperature maps. The values listed are median values in the SED integration region for each galaxy.

Method	$T_D \pm \Delta T_D$ [K]	$\beta \pm \Delta\beta$	χ^2
LMC:			
free β	21.0±1.9	1.48±0.25	1.91
fixed β	20.7±1.7	1.5 [†]	1.73
fixed β	19.2±1.6	1.8	1.63
fixed β	18.3±1.6	2.0	1.57
dustem	17.7±1.6	–	1.60
SMC:			
free β	22.3±2.3	1.21±0.27	2.28
fixed β	21.6±1.9	1.2 [†]	1.90
fixed β	18.8±1.7	1.8	9.94
fixed β	17.9±1.6	2.0	14.0
dustem	17.3±1.6	–	12.66

[†] fixed β model used in this paper.

LMC and the SMC average out to a small but positive contribution when integrated over the extent of the galaxies. We note that an excess emission remains in the SMC independently of the dust model used and the assumptions made on the free-free or synchrotron emission. The shape and intensity of the millimetre excess can change accordingly, but we could not find a solution where the SMC SED is explained purely by thermal dust emission, free-free and synchrotron. We emphasize also that the dust model, used to reproduce the dust emission up to the sub-millimetre, assumes components heated by a radiation field 10 times lower than the solar neighborhood radiation field. Compared to other nearby galaxies, this result is rather extreme ([Draine et al. 2007](#); [Bot et al. 2010b](#)).

The integrated SED of the LMC and SMC after CMB and foreground subtraction are compared in Fig. 6. These SED were computed in the same integration region as those in Fig. 5. The comparison in Fig. 6 shows that the SMC SED is flatter than the LMC one in the submm, while the SEDs when normalized in the FIR, reconcile above 10 mm, where the emission is presumably dominated by free-free and/or spinning dust (see Sec. 5).

The SEDs at various stages of the background and foreground subtraction are given in Table 2 for the LMC and SMC. The uncertainties given include the contribution from the data variance combined for the integration region, the data variance combined for the background region, and the absolute calibration uncertainties, using the values given in Table 1. They also include the noise resulting from the background (CMB) subtraction and from the foreground MW subtraction and the free-free removal. All uncertainty contributions were added quadratically.

4. Dust temperature and emissivity

4.1. Temperature determination

As shown by several previous studies (e.g. [Reach et al. 1995](#); [Finkbeiner et al. 1999](#); [Paradis et al. 2009](#); [The Planck Collaboration 2011s,t](#)), the dust emissivity spectrum in our Galaxy cannot be represented by a single dust emissivity index β over the full FIR-submm domain. The data available indicate that β is usually stronger (steeper emissivity) in the FIR and lower (flatter emissivity) in the submm, with a transition around 500 μm (see [Paradis et al. 2009](#); [The Planck Collaboration](#)




Fig. 5. Integrated SEDs of the LMC (left) and SMC (right) before and after CMB subtraction. The black points and model are taken from Bot et al. (2010b). The red symbols show the SEDs derived from the *DIRBE*, *IRAS*, and *WMAP* data before CMB subtraction. The blue symbols show the same after CMB subtraction.

Table 2. LMC (column 2-4) and SMC (column 5-7) SEDs averaged in a circular region for each galaxy. The integration region is centered on $\alpha_{2000} = 05^{\text{h}}15^{\text{m}}30^{\text{s}}$, $\delta_{2000} = -68^{\circ}30'10''$, with radius $R_{\text{LMC}} = 4.09^{\circ}$ for the LMC and centered on $\alpha_{2000} = 01^{\text{h}}04^{\text{m}}16^{\text{s}}$, $\delta_{2000} = -72^{\circ}51'36''$, with radius $R_{\text{SMC}} = 2.38^{\circ}$ for the SMC. A common background was subtracted in a 1° annulus around this region. Brightness values are in MJy sr^{-1} in the $\nu I_{\nu} = \text{cste}$ flux convention. The last two lines give the average H_{α} emission (in Rayleigh), Galactic HI emission (in K kms^{-1}) in the same area. The table lists the total SED (I_{ν}^{tot}), the CMB subtracted SED (I_{ν}^{noCMB}) and the CMB, MW foreground and free-free subtracted SED (I_{ν}^{sub}) and their associated 1σ uncertainties.

λ [μm]	I_{ν}^{tot} [MJy sr $^{-1}$]	I_{ν}^{noCMB} [MJy sr $^{-1}$]	I_{ν}^{sub} [MJy sr $^{-1}$]	I_{ν}^{tot} [MJy sr $^{-1}$]	I_{ν}^{noCMB} [MJy sr $^{-1}$]	I_{ν}^{sub} [MJy sr $^{-1}$]
IRAS :						
12	$(2.36\pm0.12)\times10^{-1}$	$(2.36\pm0.12)\times10^{-1}$	$(2.34\pm0.13)\times10^{-1}$	$(1.37\pm0.11)\times10^{-2}$	$(1.37\pm0.11)\times10^{-2}$	$(-2.79\pm0.27)\times10^{-2}$
25	$(6.28\pm0.95)\times10^{-1}$	$(6.28\pm0.95)\times10^{-1}$	$(6.25\pm0.96)\times10^{-1}$	$(7.01\pm1.10)\times10^{-2}$	$(7.01\pm1.10)\times10^{-2}$	$(5.30\pm0.98)\times10^{-2}$
60	5.79 ± 0.60	5.79 ± 0.60	5.78 ± 0.61	1.52 ± 0.16	1.52 ± 0.16	1.56 ± 0.18
100	$(1.13\pm0.15)\times10^1$	$(1.13\pm0.15)\times10^1$	$(1.13\pm0.15)\times10^1$	2.56 ± 0.35	2.56 ± 0.35	2.82 ± 0.39
Planck:						
349.82	4.97 ± 0.35	4.97 ± 0.35	4.96 ± 0.35	1.18 ± 0.08	1.18 ± 0.08	1.46 ± 0.11
550.08	1.79 ± 0.13	1.79 ± 0.13	1.78 ± 0.13	$(5.02\pm0.37)\times10^{-1}$	$(4.99\pm0.37)\times10^{-1}$	$(5.96\pm0.45)\times10^{-1}$
849.27	$(4.61\pm0.10)\times10^{-1}$	$(4.58\pm0.10)\times10^{-1}$	$(4.51\pm0.10)\times10^{-1}$	$(1.63\pm0.04)\times10^{-1}$	$(1.47\pm0.04)\times10^{-1}$	$(1.69\pm0.05)\times10^{-1}$
1381.5	$(1.16\pm0.02)\times10^{-1}$	$(1.10\pm0.03)\times10^{-1}$	$(1.04\pm0.03)\times10^{-1}$	$(7.12\pm0.18)\times10^{-2}$	$(4.30\pm0.19)\times10^{-2}$	$(4.63\pm0.20)\times10^{-2}$
2096.4	$(3.56\pm0.08)\times10^{-2}$	$(3.13\pm0.10)\times10^{-2}$	$(2.51\pm0.09)\times10^{-2}$	$(3.71\pm0.10)\times10^{-2}$	$(1.54\pm0.11)\times10^{-2}$	$(1.54\pm0.11)\times10^{-2}$
2997.9	$(1.81\pm0.05)\times10^{-2}$	$(1.53\pm0.06)\times10^{-2}$	$(8.96\pm0.48)\times10^{-3}$	$(2.25\pm0.07)\times10^{-2}$	$(8.29\pm0.71)\times10^{-3}$	$(7.09\pm0.69)\times10^{-3}$
4285.7	$(1.14\pm0.07)\times10^{-2}$	$(9.87\pm0.68)\times10^{-3}$	$(3.34\pm0.36)\times10^{-3}$	$(1.24\pm0.09)\times10^{-2}$	$(4.55\pm0.61)\times10^{-3}$	$(3.16\pm0.54)\times10^{-3}$
6818.2	$(9.24\pm0.52)\times10^{-3}$	$(8.57\pm0.51)\times10^{-3}$	$(1.72\pm0.17)\times10^{-3}$	$(6.37\pm0.49)\times10^{-3}$	$(2.94\pm0.34)\times10^{-3}$	$(1.57\pm0.28)\times10^{-3}$
10000	$(8.43\pm0.61)\times10^{-3}$	$(8.17\pm0.60)\times10^{-3}$	$(1.05\pm0.25)\times10^{-3}$	$(3.87\pm0.55)\times10^{-3}$	$(2.53\pm0.49)\times10^{-3}$	$(1.10\pm0.41)\times10^{-3}$
WMAP :						
3200	$(1.61\pm0.04)\times10^{-2}$	$(1.36\pm0.05)\times10^{-2}$	$(7.23\pm0.43)\times10^{-3}$	$(2.10\pm0.08)\times10^{-2}$	$(8.28\pm0.80)\times10^{-3}$	$(7.07\pm0.79)\times10^{-3}$
4900	$(1.04\pm0.02)\times10^{-2}$	$(9.13\pm0.23)\times10^{-3}$	$(2.51\pm0.17)\times10^{-3}$	$(1.06\pm0.03)\times10^{-2}$	$(4.32\pm0.33)\times10^{-3}$	$(2.92\pm0.31)\times10^{-3}$
7300	$(9.15\pm0.13)\times10^{-3}$	$(8.56\pm0.15)\times10^{-3}$	$(1.66\pm0.09)\times10^{-3}$	$(6.12\pm0.15)\times10^{-3}$	$(3.09\pm0.16)\times10^{-3}$	$(1.67\pm0.15)\times10^{-3}$
9100	$(9.38\pm0.12)\times10^{-3}$	$(8.98\pm0.13)\times10^{-3}$	$(1.93\pm0.06)\times10^{-3}$	$(5.10\pm0.11)\times10^{-3}$	$(3.04\pm0.11)\times10^{-3}$	$(1.63\pm0.10)\times10^{-3}$
13000	$(9.38\pm0.11)\times10^{-3}$	$(9.19\pm0.12)\times10^{-3}$	$(1.88\pm0.05)\times10^{-3}$	$(3.62\pm0.08)\times10^{-3}$	$(2.52\pm0.09)\times10^{-3}$	$(1.07\pm0.07)\times10^{-3}$
H_{α} (R):						
–	$(1.93\pm0.19)\times10^1$			7.00 ± 0.72		
$W_{\text{HI}}^{\text{MW}}$ (Kkms $^{-1}$):						
–	1.01 ± 0.13			$(-2.57\pm0.26)\times10^{+1}$		

2011t). This is likely to be the case also for the LMC and the SMC. The dust temperature derived will depend on the assumptions made about β , since these two parameters are somewhat degenerate in χ^2 space. Note that some of the past attempts at constraining the equilibrium temperature of the large grains in the LMC used the *IRAS* 60 μm emission. Emission at 60 μm is highly contaminated by out-of-equilibrium emission from

Very Small Grains (VSGs) and this is even more the case in the Magellanic Clouds, due to the presence of the 70 μm excess (Bot et al. 2004; Bernard et al. 2008). Combining the *IRAS* 60 μm and 100 μm data therefore strongly over-estimates the temperature and accordingly under-estimates the abundances of all types of dust particles. A good sampling at frequencies dominated by Big Grain (BG) emission became possible using the combination of




Fig. 6. Integrated SEDs of the LMC (solid) and SMC (dashed) after CMB and galactic foreground subtraction, including data from *Planck*-HFI (red), *Planck*-LFI (green), *IRAS* – *IRIS* (light blue) and *WMAP* (dark blue). The uncertainties shown are $\pm 3\sigma$. The SMC SED was scaled by a factor 4 providing normalization at 100 μm .

the *IRAS* and *Spitzer* data (Leroy et al. 2007; Bolatto et al. 2007; Bernard et al. 2008; Sandstrom et al. 2010).

As dust temperature is best derived from the FIR data, we limit the range of frequencies used in the determination to the FIR, which limits the impact of potential changes of the dust emissivity index β with frequency. In the determination of the dust temperature (T_D), we used the *IRAS*-*IRIS* 100 μm map and the two highest *HFI* frequencies at 857 and 545 GHz. Temperature maps were derived at the common resolution of the 3 bands used ($5''$) and at lower resolution for further analysis. In each case, the emission was computed in the photometric channels of the instruments used (*IRAS*, *Planck*, and *WMAP*), including the color corrections, using the actual transmission profiles for each instrument, and following the flux convention description given in the respective explanatory supplements.

In order to derive the thermal dust temperature, we use the same strategy as described in The Planck Collaboration (2011s). To minimise computation time, the predictions of the model were tabulated for a large set of parameters (T_D , β). For each map pixel, the χ^2 was computed for each entry of the table and the shape of the χ^2 distribution around the minimum value was used to derive the uncertainty on the free parameters. This includes the effect of the data variance σ_{II}^2 and the absolute uncertainties.

We explored several options for deriving maps of the apparent dust temperature, which are summarized in Table 3.

We first fitted each pixel of the maps with a modified black body of the form $I_\nu \propto \nu^\beta B_\nu(T_D)$ in the above spectral range (method referred to as “free β ” in Table 3). The median values of T_D and β derived using this method are given in the first line of Table 3. This led to median β values of $\beta_{\text{LMC}} \approx 1.5$ and $\beta_{\text{SMC}} \approx 1.2$ for the LMC and SMC respectively. Note that the value for the LMC is consistent with that derived using a combination of the *IRAS* and *Herschel* data by Gordon et al. (2010). However, inspection of the corresponding maps shows correlated variations of the two parameters which are also correlated with the noise level in the maps. This suggests that the spurious values probably originate from the correlation in parameter

space and the presence of noise in the data, particularly in low brightness regions of the maps.

We then performed fits of the FIR emission using the fixed β values, with the β values given above for the two galaxies (method referred to as “fixed β ” and marked with a † in Table 3). Although the median reduced χ^2 was slightly higher than for the “free β ” method, the temperature maps showed fewer spurious values, in particular in low brightness regions. This resulted in a more coherent distribution of the temperature values than in the “free β ” case. Since we later used the temperature maps to investigate the spectral distribution of the dust optical depth, and the dust temperature is a source of uncertainty, we adopted the “fixed β ” method maps in what follows. The corresponding temperature maps for the LMC and SMC are shown in Fig. 7.

The calculations were also carried out for $\beta = 1.8$, which is the average Galactic value (The Planck Collaboration 2011s,t), in order to be able to derive dust emissivity values under the same assumption as in the MW. We also experimented using the “standard” $\beta=2$ value.

4.2. Angular distribution of dust temperature

4.2.1. LMC

The temperature map derived here for the LMC shows a similar distribution to the one derived from *IRAS* and *Spitzer* data by Bernard et al. (2008). The highest temperatures are observed toward 30-Dor and are of the order of 24 K. The large scale distribution shows the existence of an inner warm arm, which follows the distribution of massive star formation as traced by known H II regions. Figure 8 shows that the warm dust at $T_D > 20$ K in the LMC is reasonably well correlated with H_α emission, indicating that it is heated by the increased radiation field induced by massive star formation. Two regions departing from the correlation are visible to the SW of the 30-Dor at $\alpha_{2000}=05^{\text{h}}40^{\text{m}}$, $\delta_{2000}=-70^\circ30'$ and $\alpha_{2000}=05^{\text{h}}40^{\text{m}}$, $\delta_{2000}=-72^\circ30'$. The first region was already identified in Bernard et al. (2008) who showed that this low column density region was unexpectedly warm given that no star formation is taking place in this area. They proposed that this could be an artifact of the *IRAS*-*IRIS* 100 μm used in the analysis, possibly due to *IRAS* gain variations upon passage on the bright 30-Dor source. However, the analysis carried out here and the comparison between temperature maps obtained with and without MW background subtraction favors a biased temperature due to low surface brightness. This points to the necessity of correcting for temperature bias at low brightness. The second region is close to the edge of the map and is probably also affected by low surface brightness.

The *Planck* data however reveals cold regions in the outer regions of the LMC, which were not seen using the *Spitzer* data. This is essentially due to the large coverage of the *Planck* data with respect to the limited region, which was covered by the *Spitzer* data. The south of the LMC exhibits a string of cold regions with $T_D < 20$ K. These regions correspond without exception to known molecular clouds when they fall in the region covered by the CO survey. They also correspond to peaks of the dust optical depth as derived in the following sections. Similarly, a set of cold regions exist at the northwest periphery of the LMC. The comparison with the distribution of CO clouds is shown in Fig. 8. As already noticed in Bernard et al. (2008), there is no systematic correlation between cold dust and the presence of molecular material, at least in the inner regions of the LMC. This was confirmed by the statistical characteristics of the IR properties of LMC molecular clouds established by Paradis et al.




Fig. 7. Upper panels: Dust temperature maps for the LMC (left) and SMC (right) computed from the foreground subtracted maps using the *IRIS-IRIS* 100 μm , *HFI* 857 and 545 GHz maps, using a fixed $\beta_{LMC} = 1.5$ and $\beta_{SMC} = 1.2$. Lower panels: relative uncertainties on the dust temperature at the same resolution, expressed as percentages.

(2010), which showed no systematic trend for molecular regions to be colder than their surrounding neutral material. However, toward the outer regions of the LMC, molecular clouds appear systematically to show a decrease in the dust temperature. This difference may be due to the absence of star formation activity in the outer regions and/or to less mixing along the line of sight.

Gordon et al. (2010) derived a dust temperature map from the *Herschel* data (HERITAGE program) for a fraction of the LMC observed during the Science Demonstration Phase (SDP). They used the 100 μm to 350 μm *IRAS* and *Herschel* bands to constrain the temperature. They found that the temperatures derived this way only differ from those derived by Bernard et al. (2008) by up to 10%. The SDP field covered an elongated region across the LMC roughly oriented north–south. This strip crossed the warm inner arm, which is also clearly seen in their map. However, we stress that, in their study, a gradient was removed along the strip based on the values at the edges. The fact that we detect significantly colder than average dust in the outer cold arm of the LMC underlines the need to take those variations into account when subtracting background emission in the *Herschel* data.

4.2.2. SMC

The temperature map derived for the SMC shows more moderate temperature variations than those observed in the LMC but peaks corresponding to well known HII regions are clearly identified, and the overall dust temperature correlates with H_α emission, as shown in Fig. 9. In particular, the massive star forming region SMC-N66 (Henize 1956) ($\alpha_{2000}=00^{\text{h}}59^{\text{m}}27.40^{\text{s}}$, $\delta_{2000}=-72^{\circ}10'11''$) corresponds to the highest temperature (~ 20 K) in the SMC. Other well known star forming regions like SMC-N83/84 ($01^{\text{h}}14^{\text{m}}21.0^{\text{s}}$, $-73^{\circ}17'12''$), N81 ($01^{\text{h}}09^{\text{m}}13.6^{\text{s}}$, $-73^{\circ}11'41''$), N88/89/90 (in the wing: $01^{\text{h}}24^{\text{m}}08.1^{\text{s}}$, $-73^{\circ}08'55''$) and DEM S54 (at the center of the main bar: $00^{\text{h}}50^{\text{m}}25.9^{\text{s}}$, $-72^{\circ}53'10''$) appear as temperature peaks compared to the surroundings. In contrast, the infrared-bright star forming region N76 (located at the northeast of N66: $01^{\text{h}}04^{\text{m}}01.2^{\text{s}}$, $-72^{\circ}01'52''$) and southwest star-forming complex do not stand out. This could be due to the presence of an extended warm component that we observe in the main bar and that seems spatially related to the diffuse H_α emission.




Fig. 8. Comparison between the dust temperature map of the LMC with H_α (top) and CO emission (bottom). The CO contours are at 0.5, 2, 4 and 10 K km s^{-1} . H_α contours are at 1, 10, 50, 100, 500 and 1000 Rayleigh. The thick line shows the edge of the available CO surveys.

4.3. Optical depth determination

Optical depth is derived using:

$$\tau(\nu) = \frac{I_\nu}{B_\nu(T_d)}, \quad (1)$$

where B_ν is the Planck function. We used resolution matched maps of T_D and I_ν and derived τ maps at the various resolutions of the data used here. The uncertainty on τ ($\Delta\tau$) is computed accordingly as:

$$\Delta\tau(\nu) = \tau \left(\frac{\sigma_{II}^2}{I_\nu^2} + \left(\frac{\delta B_\nu(T_D)}{\delta T} \frac{\Delta T_D}{B_\nu(T_D)} \right)^2 \right)^{1/2}. \quad (2)$$

The optical depth and optical depth uncertainty maps derived at 857 GHz are shown in Fig. 10 and Fig. 11 for the LMC and the SMC respectively.




Fig. 9. Comparison between the dust temperature map of the SMC with H_α (top) and CO emission (bottom). The CO contours are at 0.5, 1 and 1.5 K km s^{-1} . H_α contours are at 1, 5, 30 and 100 Rayleigh. The thick line shows the edge of the available CO surveys.

5. Discussion

5.1. The millimetre excess

Bot et al. (2010b) (see Fig. 5) found that the integrated SED of the LMC and more noticeably of the SMC showed excess millimetre emission with respect to a dust and free-free/synchrotron model based respectively on the FIR and the radio data available. They investigated several causes for this excess. They noticed that the excess had precisely the colors of CMB fluctuations. They performed simulations by placing the LMC and SMC structure at various positions over a CMB simulated sky, and concluded that a CMB origin was unlikely, but not excluded. Other proposed origins for the excess included the presence of very cold dust, spinning dust or large modifications of the optical properties of thermal dust.




Fig. 10. Upper panel: Map of the dust optical depths of the LMC at *HFI* 217 GHz. Units are $10^4 \times \tau$. Lower panel: Map of the dust optical depth relative uncertainty of the LMC at *HFI* 217 GHz in percent. Black pixels in the maps are masked and have relative uncertainties larger than 50%.




Fig. 11. Upper panel: Map of the dust optical depths of the SMC at *HFI* 217 GHz. Units are $10^4 \times \tau$. Lower panel: Map of the dust optical depth relative uncertainty at *HFI* 217 GHz in percent. Black pixels in the maps are masked and have relative uncertainties larger than 50%.

Very cold dust ($T_D \simeq 5 - 7$ K) has been advocated to explain the flattening of the millimetre emission observed in more distant low metallicity galaxies (e.g. [Galliano et al. 2005](#)). However, this usually led to very large masses, and the existence of such very cold dust remains controversial and difficult to understand in low metallicity systems where the stronger star formation rate and the lower dust abundances prevents efficient screening from UV photons.

[Bot et al. \(2010b\)](#) applied spinning dust models to fit the SMC and LMC SEDs and found a plausible match. However, since the observed excess peaked at a significantly higher frequency than observed for spinning dust in other regions (e.g. [The Planck Collaboration 2011v](#)), their fit required extreme density and excitation conditions for the small dust particles.

Using the Two Level System model by [Meny et al. \(2007\)](#) for the long wavelength emission of amorphous solids also proved

plausible for the LMC, but a convincing fit could not be found for the SMC, essentially because the model could not reproduce the shape of the excess.

The study carried out here, which takes advantage of the *Planck* measurements to constrain the CMB foreground fluctuations towards the two galaxies, shows that part of the excess observed toward the SMC cannot be accounted for by the fluctuations of the background CMB, as discussed in [Sec. 2.3.2](#), but the intensity of the excess has been greatly reduced compared to the one found by [Bot et al. \(2010b\)](#).

To give more insight into this excess, we built a map to trace the spatial distribution of the excess emission in the SMC. To do so, we applied the fitting procedure performed for the integrated SEDs of the Magellanic Cloud, to each point of the SMC at the angular resolution of the *LFI* smallest frequency channel. The SEDs were built at each point using the CMB and foreground–




Fig. 12. Map of the millimetre excess in the SMC at 3 mm computed at the resolution of the *LFI* -28.5 GHz channel, after free-free subtraction. The contours show the H_α distribution.

subtracted data. To model the SEDs, we assumed that, at each point, the SEDs are dominated by free-free and dust emission up to the longest wavelengths covered by *Planck*, following what is observed for the integrated emission of the SMC (see Fig. 5). The free-free component at each wavelength was extrapolated from the H_α emission (as in Sect. 3), assuming that the extinction in the SMC is negligible. The thermal dust emission was then fitted to the data points at $\lambda_{\text{ref}} < 550 \mu\text{m}$, using the [Draine et al. \(2007\)](#) dust model. The millimeter excess was then defined as the difference between the data and the dust-and-free-free model. The resulting spatial distribution of the excess emission at 100 GHz (3 mm) is shown in Fig. 12. This shows that the peak of the excess is located at the southwest tip of the bar. This region also corresponds to the maximum of the optical depth derived from the FIR and shown in Fig. 11 and the overall excess spatial distribution is consistent with being proportional to the dust column density.

5.2. FIR dust emissivity

The wavelength dependence of the average dust optical depth in the LMC and SMC is shown in Fig. 13. The spectral index of the emissivity in the FIR is consistent with $\beta = 1.5$ and $\beta = 1.2$ for the LMC and the SMC respectively. This value for the LMC is consistent with findings by [Gordon et al. \(2010\)](#) using the *Herschel* data. We see no hint for a change of the spectral index with wavelength for the LMC. In contrast, the SMC SED clearly flattens at $\lambda > 800 \mu\text{m}$ to reach extremely flat β values around $\lambda = 3 \text{ mm}$. The dust emissivities as interpolated using the power laws shown in Fig. 13 can be compared to the reference value for the solar neighborhood of $\tau/N_H = 10^{-25} \text{ cm}^2$ at $250 \mu\text{m}$ ([Boulanger et al. 1996](#)). This comparison indicates lower than solar dust abundances for the two galaxies, by about 1/2.4 and 1/13 solar respectively. This is in rough agreement with metallicity for the LMC and significantly lower than metallicity for the SMC.

[Gordon et al. \(2010\)](#) found hints of such excess emission around $500 \mu\text{m}$ in the LMC *Herschel* data, but this remained within the current calibration uncertainties of the *Herschel* Spectral and Photometric Imaging Receiver (*SPIRE*) instrument. We also observe that the $500 \mu\text{m}$ optical depth of the LMC is slightly higher (by 8.4%) than the power law extrapolation shown in Fig. 13, but this is only marginally larger than the 1σ uncertainty at this wavelength. In any case, data points at longer wavelengths do not support the existence of excess emission in addition to a $\beta = 1.5$ power law for the LMC.




Fig. 13. Average dust optical depth of the LMC (black) and SMC (blue) obtained from the CMB, foreground and free-free subtracted SEDs. The average is taken in the same regions as for Fig. 5. The SMC SED was normalized (multiplied by 6.31) to that of the LMC at $100 \mu\text{m}$. The square symbol (green) shows the reference value for the solar neighborhood by [Boulanger et al. \(1996\)](#). The dashed lines show $\tau \propto \nu^{1.5}$ and $\tau \propto \nu^{1.2}$ normalized at $100 \mu\text{m}$. Error bars are $\pm 3\sigma$.

5.3. Possible interpretation of the excess

In this section, we attempt to fit the SED of the SMC using various models which have been proposed to explain excess submm emission in addition to a single dust emissivity power-law for thermal dust. Figure 14 shows several fits to the FIR-Submm SED of the SMC.

The first fit uses the [Finkbeiner et al. \(1999\)](#) model #7 (see their Table 3), which was designed to explain the flatter than expected emission spectrum of our Galaxy as observed by *FIRAS*. Here we use this model to assess the possibility that the millimeter excess is due to very cold dust. The model was fitted using the same β values as in [Finkbeiner et al. \(1999\)](#) for the two dust components ($\beta_{\text{warm}} = 2.6$, $\beta_{\text{cold}} = 1.5$). It also assumes the same type of relationship between the cold and warm dust temperatures, which in the model reflects the fact that both dust species are subjected to the same radiation field. However, we allow the IR/optical opacity ratio ($q_{\text{cold}}/q_{\text{warm}}$) to vary, so that the ratio between the warm and cold dust temperatures is free to vary. We also leave the cold dust component abundance (f_{cold}) and the warm dust temperature (T_{warm}) as free parameters. The best fit values are found for $T_{\text{warm}} = 16.4 \text{ K}$, $q_{\text{cold}}/q_{\text{warm}} = 168.2$, $f_{\text{cold}} = 8.7 \cdot 10^{-3}$. For these parameters, the temperature of the cold component is $T_{\text{cold}} = 5.9 \text{ K}$. This cold temperature is needed to reproduce part of the millimetre excess




Fig. 14. Fit of the SMC SED using the Finkbeiner model (upper left), the TLS model (upper right), the spinning dust model (lower left) and a combination of TLS and spinning dust models (lower right). In the lower panels, the squares represent the flux in each band predicted by the best model (the blue line).

but is much colder than that obtained by Finkbeiner et al. (1999) for the Galaxy ($T_{\text{cold}} = 9.6$ K). This is obtained at the expense of strongly increasing the IR/optical opacity ratio for the cold component ($q_{\text{cold}}/q_{\text{warm}}$ increased by a factor 15), which controls the $T_{\text{cold}}/T_{\text{warm}}$ ratio. The mass fraction of the cold component derived here, f_{cold} , is about 4 times lower than that derived for the MW in Finkbeiner et al. (1999), which compensates for the increased $q_{\text{cold}}/q_{\text{warm}}$. It is apparent that, despite invoking a much larger IR/optical opacity ratio for the cold particles, such a model has difficulties producing the submm excess above about $\lambda = 2$ mm.

The second fit employs the Two-Level-System (TLS) model developed by Meny et al. (2007). The fit was obtained by minimizing χ^2 in the range $100 \mu\text{m} < \lambda < 5$ mm against the following 3 parameters: T_{D} the dust temperature, l_{cor} the correlation length of defects in the material and A the density of TLS sites in the material composing the grains. The values derived for these parameters are $T_{\text{D}}=18.9$ K, $l_{\text{cor}}=12.85$ nm and $A=7.678$. The reduced χ^2 for these parameters is $\chi^2=2.56$. Compared to the best values found from Paradis (2007) for the MW ($T_{\text{D}}=17.9$ K, $l_{\text{cor}}=12.85$ nm, $A=2.42$), this indicates dust material with more TLS sites (more mechanical defects) but a similar defect correlation length compared with the dust dominating the MW emission. Note that a grey-body fit of the same SED over the same

frequency range leads to $T_{\text{D}}=18.9$ K and $\beta=0.74$ and a reduced $\chi^2=6.12$, showing that the TLS model reproduces the data better than a single grey-body fit.

The third fit uses spinning dust. In that case, the thermal dust emission was reproduced using the Draine & Li (2007) dust model. The remaining excess is then fitted with the spinning dust model described in Silsbee et al. (2010). Spinning dust emission has been proved to be sensitive to the neutral and ionized gas densities and to the size distribution of dust grains. The radiation field and the size distributions are taken to be the same as for the Draine & Li (2007) model. The relevant gas parameters are computed with CLOUDY (Ferland et al. 1998): we take the parameters from the optically thin zone of isochoric simulations. In both cases, we take into account the lower metallicity and dust grains abundance when compared to the MW. The electric dipole moment distribution of grains is taken as in Draine & Lazarian (1998b)². This fit is obtained by adding two components according to the PDR fraction inferred from the thermal emission model: a diffuse medium with $n_{\text{H}}=30 \text{ cm}^{-3}$ and 100% of the PAH mass expected from the IR modeling, and a

² Ysard & Verstraete (2010b) showed that it is in good agreement with the anomalous emission extracted from the *WMAP* data.

denser medium with $n_{\text{H}}=5000\text{ cm}^{-3}$ and 82% of the PAH mass expected.

The fourth one is a combination of the TLS model and the spinning dust model presented above.

It is clear from Fig. 14 that the model combining TLS and spinning dust is the only one of the proposed models giving a satisfactory fit to the millimetre excess observed in the SMC over the whole spectral range. In addition, it alleviates the need for using more PAH than allowed by the NIR emission to produce the required level of spinning dust emission observed. Alternative models, however, cannot be excluded. For instance, very large grains ($a > 30\text{ }\mu\text{m}$) that would be efficient radiators (Rowan-Robinson 1992) could create emission in the millimetre wavelengths without too much mass. Exploring this possibility would require specific modeling. This is beyond the scope of the current article but should be explored in future studies.

6. Conclusions

We assessed the existence and investigated the origin of millimetre excess emission in the LMC and the SMC using the *Planck* data. The integrated SED of the two galaxies before subtraction of the foreground (Milky Way) and background (CMB fluctuations) emission are in good agreement with previous determinations.

The background CMB contribution was first subtracted using an Internal Linear Combination (ILC) method performed locally around the two galaxies. The uncertainty of this contribution was measured through a detailed Monte-Carlo simulation. We subtracted the foreground emission from the Milky Way using a Galactic H I template and the proper dust emissivity derived in a region surrounding the two galaxies and dominated by MW emission. We also subtracted the free-free contribution from ionized gas in the galaxies, using the $\text{H}\alpha$ emission, taking advantage of the low extinction in those galaxies. The remaining emission of both galaxies correlates with the gas emission of the LMC and SMC.

We showed that the excess previously reported in the LMC can be fully explained by CMB fluctuations. For the SMC, subtracting the CMB fluctuations decreases the intensity of the excess but a significant millimetre emission above the expected thermal dust, free-free and synchrotron emission remains.

We combined the *Planck* and *IRAS-IRIS* data at $100\text{ }\mu\text{m}$ to produce thermal dust temperature and optical depth maps of the two galaxies. The LMC temperature map shows the presence of a warm inner arm already found with the *Spitzer* data, but also shows the existence of a previously unidentified cold outer arm. Several cold regions were found along this arm, some of which are associated to known molecular clouds.

We used the dust optical depth maps to constrain the thermal dust emissivity spectral index (β). The average spectral index in the FIR ($\lambda < 500\text{ }\mu\text{m}$) is found to be consistent with $\beta = 1.5$ and $\beta = 1.2$ for the LMC and the SMC respectively. This is significantly flatter than what is observed in the Milky Way. The absolute values of the emissivities in the FIR, when compared to that in our solar neighborhood, are compatible with D/G mass ratio of 1/2.4 and 1/13 for the LMC and SMC. This is compatible with the metallicity for the LMC but significantly lower than metallicity for the SMC. In the submm, the LMC SED remains consistent with $\beta = 1.5$, while the SED of the SMC flattens even more.

The spatial distribution of the mm excess in the SMC appears to follow the general pattern of the gas distribution. It therefore appears unlikely that the excess could originate from very cold

dust. Indeed, this is confirmed by attempts to fit the SMC emission SED with 2 dust component models, which led to poor fits. Alternative models, such as emission excess due to the amorphous nature of large grains are likely to provide a natural explanation to the observed SED, although spinning dust is needed to explain the SED above $\lambda = 3\text{ mm}$.

Acknowledgements. A description of the Planck Collaboration and a list of its members can be found at http://www.rssd.esa.int/index.php?project=PLANCK&page=Planck_Collaboration

References

- Anderson, N. & Watson, W. D. 1993, *A&A*, 270, 477
 Bendo, G. J., Dale, D. A., Draine, B. T., et al. 2006, *ApJ*, 652, 283
 Bennett, C. L., Halpern, M., Hinshaw, G., et al. 2003, *ApJS*, 148, 1
 Bernard, J., Reach, W. T., Paradis, D., et al. 2008, *AJ*, 136, 919
 Bolatto, A. D., Simon, J. D., Stanimirović, S., et al. 2007, *ApJ*, 655, 212
 Bot, C., Boulanger, F., Lagache, G., Cambrésy, L., & Egret, D. 2004, *A&A*, 423, 567
 Bot, C., Rubio, M., Boulanger, F., et al. 2010a, *A&A*, 524, A52+
 Bot, C., Ysard, N., Paradis, D., et al. 2010b, *A&A*, 523, A20+
 Boulanger, F., Abergel, A., Bernard, J., et al. 1996, *A&A*, 312, 256
 Dobashi, K., Bernard, J., Hughes, A., et al. 2008, *A&A*, 484, 205
 Draine, B. T., Dale, D. A., Bendo, G., et al. 2007, *ApJ*, 663, 866
 Draine, B. T. & Lazarian, A. 1998a, *ApJ*, 494, L19+
 Draine, B. T. & Lazarian, A. 1998b, *ApJ*, 508, 157
 Draine, B. T. & Li, A. 2007, *ApJ*, 657, 810
 Dumke, M., Krause, M., & Wielebinski, R. 2003, in *Revista Mexicana de Astronomía y Astrofísica*, vol. 27, Vol. 17, *Revista Mexicana de Astronomía y Astrofísica Conference Series*, ed. V. Avila-Reese, C. Firmani, C. S. Frenk, & C. Allen, 185–185
 Dupac, X., Bernard, J., Boudet, N., et al. 2003, *A&A*, 404, L11
 Eriksen, H. K., Banday, A. J., Górski, K. M., & Lilje, P. B. 2004, *ApJ*, 612, 633
 Ferland, G. J., Korista, K. T., Verner, D. A., et al. 1998, *PASP*, 110, 761
 Ferrara, A. & Dettmar, R. 1994, *ApJ*, 427, 155
 Finkbeiner, D. P., Davis, M., & Schlegel, D. J. 1999, *ApJ*, 524, 867
 Fukui, Y., Kawamura, A., Minamidani, T., et al. 2008, *ApJS*, 178, 56
 Fukui, Y., Mizuno, N., Yamaguchi, R., et al. 1999, *PASJ*, 51, 745
 Galametz, M., Madden, S., Galliano, F., et al. 2009, *A&A*, 508, 645
 Galametz, M., Madden, S. C., Galliano, F., et al. 2010, *A&A*, 518, L55+
 Galliano, F., Madden, S. C., Jones, A. P., Wilson, C. D., & Bernard, J. 2005, *A&A*, 434, 867
 Galliano, F., Madden, S. C., Jones, A. P., et al. 2003, *A&A*, 407, 159
 Gaustad, J. E., McCullough, P. R., Rosing, W., & Van Buren, D. 2001, *PASP*, 113, 1326
 Gordon, K. D., Bot, C., Muller, E., et al. 2009, *ApJ*, 690, L76
 Gordon, K. D., Galliano, F., Hony, S., et al. 2010, *A&A*, 518, L89+
 Górski, K. M., Hivon, E., Banday, A. J., et al. 2005, *ApJ*, 622, 759
 Grossi, M., Hunt, L. K., Madden, S., et al. 2010, *A&A*, 518, L52+
 Henize, K. G. 1956, *ApJS*, 2, 315
 Hoang, T., Draine, B. T., & Lazarian, A. 2010, *ApJ*, 715, 1462
 Hunt, L. K., Dyer, K. K., Thuan, T. X., & Ulvestad, J. S. 2004, *ApJ*, 606, 853
 Israel, F. P., Wall, W. F., Raban, D., et al. 2010, *A&A*, 519, A67+
 Jarosik, N., Bennett, C. L., Dunkley, J., et al. 2010, *ArXiv e-prints*
 Kim, S., Staveley-Smith, L., Dopita, M. A., et al. 2003, *ApJS*, 148, 473
 Komatsu, E., Smith, K. M., Dunkley, J., et al. 2010, *ArXiv e-prints*
 Leroy, A., Bolatto, A., Stanimirović, S., et al. 2007, *ApJ*, 658, 1027
 Leroy, A. K., Bolatto, A., Bot, C., et al. 2009, *ApJ*, 702, 352
 Lisenfeld, U., Sievers, A., Israel, F., & Stil, J. 2001, *Astrophysics and Space Science Supplement*, 277, 105
 Madden, S. C. 2000, *New A Rev.*, 44, 249
 Madden, S. C., Poglitsch, A., Geis, N., Stacey, G. J., & Townes, C. H. 1997, *ApJ*, 483, 200
 Meixner, M., Galliano, F., Hony, S., et al. 2010, *A&A*, 518, L71+
 Meixner, M., Gordon, K. D., Indebetouw, R., et al. 2006, *AJ*, 132, 2268
 Meny, C., Gromov, V., Boudet, N., et al. 2007, *A&A*, 468, 171
 Miville-Deschênes, M. & Lagache, G. 2005, *ApJS*, 157, 302
 Mizuno, N., Rubio, M., Mizuno, A., et al. 2001, *PASJ*, 53, L45
 Muller, E., Staveley-Smith, L., Zealey, W., & Stanimirović, S. 2003, *MNRAS*, 339, 105
 O'Halloran, B., Galametz, M., Madden, S. C., et al. 2010, *A&A*, 518, L58+
 O'Halloran, B., Madden, S. C., & Abel, N. P. 2008, *ApJ*, 681, 1205
 Paradis, D. 2007, *PhD Thesis*
 Paradis, D., Bernard, J., & Mény, C. 2009, *A&A*, 506, 745
 Paradis, D. & et al. 2011, in preparation

- Paradis, D., Veneziani, M., Noriega-Crespo, A., et al. 2010, *A&A*, 520, L8+
- Poglitsch, A., Krabbe, A., Madden, S. C., et al. 1995, *ApJ*, 454, 293
- Reach, W. T., Dwek, E., Fixsen, D. J., et al. 1995, *ApJ*, 451, 188
- Roman-Duval, J., Israel, F. P., Bolatto, A., et al. 2010, *A&A*, 518, L74+
- Rowan-Robinson, M. 1992, *MNRAS*, 258, 787
- Sandstrom, K. M., Bolatto, A. D., Draine, B. T., Bot, C., & Stanimirović, S. 2010, *ApJ*, 715, 701
- Santini, P., Maiolino, R., Magnelli, B., et al. 2010, *A&A*, 518, L154+
- Shetty, R., Kauffmann, J., Schnee, S., & Goodman, A. A. 2009a, *ApJ*, 696, 676
- Shetty, R., Kauffmann, J., Schnee, S., Goodman, A. A., & Ercolano, B. 2009b, *ApJ*, 696, 2234
- Silsbee, K., Ali-Haïmoud, Y., & Hirata, C. M. 2010, *ArXiv e-prints*
- Stanimirovic, S., Staveley-Smith, L., Dickey, J. M., Sault, R. J., & Snowden, S. L. 1999, *MNRAS*, 302, 417
- Staveley-Smith, L., Kim, S., Calabretta, M. R., Haynes, R. F., & Kesteven, M. J. 2003, *MNRAS*, 339, 87
- Staveley-Smith, L., Sault, R. J., Hatzidimitriou, D., Kesteven, M. J., & McConnell, D. 1997, *MNRAS*, 289, 225
- The Planck Collaboration. 2011a, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011b, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011c, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011d, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011e, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011f, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011g, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011h, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011i, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011j, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011k, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011l, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011m, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011n, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011o, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011p, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011q, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011r, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011s, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011t, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011u, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011v, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011w, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011x, *ArXiv Astrophysics e-prints*
- The Planck Collaboration. 2011y, *ArXiv Astrophysics e-prints*
- Ysard, N., Miville-Deschênes, M. A., & Verstraete, L. 2010, *A&A*, 509, L1+
- Ysard, N., & Verstraete, L. 2010a, *A&A*, 509, A12+
- Ysard, N., & Verstraete, L. 2010b, *A&A*, 509, A12+
- Zhu, M., Papadopoulos, P. P., Xilouris, E. M., Kuno, N., & Lisenfeld, U. 2009, *ApJ*, 706, 941
- 0355, Santiago, Chile
- ⁵ CITA, University of Toronto, 60 St. George St., Toronto, ON M5S 3H8, Canada
- ⁶ CNRS, IRAP, 9 Av. colonel Roche, BP 44346, F-31028 Toulouse cedex 4, France
- ⁷ California Institute of Technology, Pasadena, California, U.S.A.
- ⁸ DAMTP, Centre for Mathematical Sciences, Wilberforce Road, Cambridge CB3 0WA, U.K.
- ⁹ DSM/Irfu/SPP, CEA-Saclay, F-91191 Gif-sur-Yvette Cedex, France
- ¹⁰ DTU Space, National Space Institute, Juliane Mariesvej 30, Copenhagen, Denmark
- ¹¹ Departamento de Física, Universidad de Oviedo, Avda. Calvo Sotelo s/n, Oviedo, Spain
- ¹² Department of Astronomy and Astrophysics, University of Toronto, 50 Saint George Street, Toronto, Ontario, Canada
- ¹³ Department of Astronomy and Earth Sciences, Tokyo Gakugei University, Koganei, Tokyo 184-8501, Japan
- ¹⁴ Department of Physical Science, Graduate School of Science, Osaka Prefecture University, 1-1 Gakuen-cho, Naka-ku, Sakai, Osaka 599-8531, Japan
- ¹⁵ Department of Physics & Astronomy, University of British Columbia, 6224 Agricultural Road, Vancouver, British Columbia,

¹ Aalto University Metsähovi Radio Observatory, Metsähovintie 114, FIN-02540 Kylmäla, Finland

² Agenzia Spaziale Italiana Science Data Center, c/o ESRIN, via Galileo Galilei, Frascati, Italy

³ Astroparticule et Cosmologie, CNRS (UMR7164), Université Denis Diderot Paris 7, Bâtiment Condorcet, 10 rue A. Domon et Léonie Duquet, Paris, France

⁴ Atacama Large Millimeter/submillimeter Array, ALMA Santiago Central Offices Alonso de Cordova 3107, Vitacura, Casilla 763

- | | |
|---|---|
| Canada | Villanueva de la Cañada, Madrid, Spain |
| ¹⁶ Department of Physics, Gustaf Hållströmin katu 2a, University of Helsinki, Helsinki, Finland | ³³ European Space Agency, ESTEC, Keplerlaan 1, 2201 AZ Noordwijk, The Netherlands |
| ¹⁷ Department of Physics, Nagoya University, Chikusa-ku, Nagoya, 464-8602, Japan | ³⁴ Helsinki Institute of Physics, Gustaf Hållströmin katu 2, University of Helsinki, Helsinki, Finland |
| ¹⁸ Department of Physics, Princeton University, Princeton, New Jersey, U.S.A. | ³⁵ INAF - Osservatorio Astrofisico di Catania, Via S. Sofia 78, Catania, Italy |
| ¹⁹ Department of Physics, Purdue University, 525 Northwestern Avenue, West Lafayette, Indiana, U.S.A. | ³⁶ INAF - Osservatorio Astronomico di Padova, Vicolo dell'Osservatorio 5, Padova, Italy |
| ²⁰ Department of Physics, University of California, Berkeley, California, U.S.A. | ³⁷ INAF - Osservatorio Astronomico di Roma, via di Frascati 33, Monte Porzio Catone, Italy |
| ²¹ Department of Physics, University of California, One Shields Avenue, Davis, California, U.S.A. | ³⁸ INAF - Osservatorio Astronomico di Trieste, Via G.B. Tiepolo 11, Trieste, Italy |
| ²² Department of Physics, University of California, Santa Barbara, California, U.S.A. | ³⁹ INAF/IASF Bologna, Via Gobetti 101, Bologna, Italy |
| ²³ Department of Physics, University of Illinois at Urbana-Champaign, 1110 West Green Street, Urbana, Illinois, U.S.A. | ⁴⁰ INAF/IASF Milano, Via E. Bassini 15, Milano, Italy |
| ²⁴ Dipartimento di Fisica G. Galilei, Università degli Studi di Padova, via Marzolo 8, 35131 Padova, Italy | ⁴¹ INRIA, Laboratoire de Recherche en Informatique, Université Paris-Sud 11, Bâtiment 490, 91405 Orsay Cedex, France |
| ²⁵ Dipartimento di Fisica, Università La Sapienza, P. le A. Moro 2, Roma, Italy | ⁴² IPAG: Institut de Planétologie et d'Astrophysique de Grenoble, Université Joseph Fourier, Grenoble 1 / CNRS-INSU, UMR 5274, Grenoble, F-38041, France |
| ²⁶ Dipartimento di Fisica, Università degli Studi di Milano, Via Celoria, 16, Milano, Italy | ⁴³ Imperial College London, Astrophysics group, Blackett Laboratory, Prince Consort Road, London, SW7 2AZ, U.K. |
| ²⁷ Dipartimento di Fisica, Università degli Studi di Trieste, via A. Valerio 2, Trieste, Italy | ⁴⁴ Infrared Processing and Analysis Center, California Institute of Technology, Pasadena, CA 91125, U.S.A. |
| ²⁸ Dipartimento di Fisica, Università di Roma Tor Vergata, Via della Ricerca Scientifica, 1, Roma, Italy | ⁴⁵ Institut d'Astrophysique Spatiale, CNRS (UMR8617) Université Paris-Sud 11, Bâtiment 121, Orsay, France |
| ²⁹ Discovery Center, Niels Bohr Institute, Blegdamsvej 17, Copenhagen, Denmark | ⁴⁶ Institut d'Astrophysique de Paris, CNRS UMR7095, Université Pierre & Marie Curie, 98 bis boulevard Arago, Paris, France |
| ³⁰ Dpto. Astrofísica, Universidad de La Laguna (ULL), E-38206 La Laguna, Tenerife, Spain | ⁴⁷ Institute of Astronomy and Astrophysics, Academia Sinica, Taipei, Taiwan |
| ³¹ European Southern Observatory, ESO Vitacura, Alonso de Cordova 3107, Vitacura, Casilla 19001, Santiago, Chile | ⁴⁸ Institute of Theoretical Astrophysics, University of Oslo, Blindern, Oslo, Norway |
| ³² European Space Agency, ESAC, Planck Science Office, Camino bajo del Castillo, s/n, Urbanización Villafranca del Castillo, | ⁴⁹ Instituto de Astrofísica de Canarias, C/Vía Láctea s/n, La Laguna, Tenerife, Spain |
| | ⁵⁰ Instituto de Física de Cantabria (CSIC-Universidad de Cantabria), Avda. de los Castros s/n, Santander, Spain |
| | ⁵¹ Jet Propulsion Laboratory, California Institute of Technology, 4800 Oak Grove Drive, Pasadena, California, U.S.A. |
| | ⁵² Jodrell Bank Centre for Astrophysics, Alan Turing Building, School of Physics and Astronomy, The University of Manchester, Oxford Road, Manchester, M13 9PL, U.K. |
| | ⁵³ Kavli Institute for Cosmology Cambridge, Madingley Road, Cambridge, CB3 0HA, U.K. |
| | ⁵⁴ LERMA, CNRS, Observatoire de Paris, 61 Avenue de l'Observatoire, Paris, France |
| | ⁵⁵ Laboratoire AIM, IRFU/Service d'Astrophysique - CEA/DSM - CNRS - Université Paris Diderot, Bât. 709, CEA-Saclay, F-91191 |

Gif-sur-Yvette Cedex, France

France

- ⁵⁶ Laboratoire Traitement et Communication de l'Information, CNRS (UMR 5141) and Télécom ParisTech, 46 rue Barrault F-75634 Paris Cedex 13, France
- ⁵⁷ Laboratoire de Physique Subatomique et de Cosmologie, CNRS, Université Joseph Fourier Grenoble I, 53 rue des Martyrs, Grenoble,
- ⁵⁸ Laboratoire de l'Accélérateur Linéaire, Université Paris-Sud 11, CNRS/IN2P3, Orsay, France
- ⁵⁹ Lawrence Berkeley National Laboratory, Berkeley, California, U.S.A.
- ⁶⁰ Max-Planck-Institut für Astrophysik, Karl-Schwarzschild-Str. 1, 85741 Garching, Germany
- ⁶¹ MilliLab, VTT Technical Research Centre of Finland, Tietotie 3, Espoo, Finland
- ⁶² National University of Ireland, Department of Experimental Physics, Maynooth, Co. Kildare, Ireland
- ⁶³ Niels Bohr Institute, Blegdamsvej 17, Copenhagen, Denmark
- ⁶⁴ Observational Cosmology, Mail Stop 367-17, California Institute of Technology, Pasadena, CA, 91125, U.S.A.
- ⁶⁵ Observatoire Astronomique de Strasbourg, CNRS, UMR7550, F-67000 Strasbourg, France
- ⁶⁶ Optical Science Laboratory, University College London, Gower Street, London, U.K.
- ⁶⁷ SISSA, Astrophysics Sector, via Bonomea 265, 34136, Trieste, Italy
- ⁶⁸ SUPA, Institute for Astronomy, University of Edinburgh, Royal Observatory, Blackford Hill, Edinburgh EH9 3HJ, U.K.
- ⁶⁹ School of Physics and Astronomy, Cardiff University, Queens Buildings, The Parade, Cardiff, CF24 3AA, U.K.
- ⁷⁰ Space Sciences Laboratory, University of California, Berkeley, California, U.S.A.
- ⁷¹ Spitzer Science Center, 1200 E. California Blvd., Pasadena, California, U.S.A.
- ⁷² Stanford University, Dept of Physics, Varian Physics Bldg, 382 Via Pueblo Mall, Stanford, California, U.S.A.
- ⁷³ Université de Toulouse, UPS-OMP, IRAP, F-31028 Toulouse cedex 4, France
- ⁷⁴ Universities Space Research Association, Stratospheric Observatory for Infrared Astronomy, MS 211-3, Moffett Field, CA 94035, U.S.A.
- ⁷⁵ University of Cambridge, Cavendish Laboratory, Astrophysics group, J J Thomson Avenue, Cambridge, U.K.
- ⁷⁶ University of Cambridge, Institute of Astronomy, Madingley Road, Cambridge, U.K.
- ⁷⁷ University of Granada, Departamento de Física Teórica y del Cosmos, Facultad de Ciencias, Granada, Spain
- ⁷⁸ University of Miami, Knight Physics Building, 1320 Campo Sano Dr., Coral Gables, Florida, U.S.A.
- ⁷⁹ Warsaw University Observatory, Aleje Ujazdowskie 4, 00-478 Warszawa, Poland